

**MUNSON TOWNSHIP WASTE WATER TREATMENT SYSTEM
MUNSON TOWNSHIP, GEAUGA COUNTY, OHIO
BID SHEET 1 OF 4**

ITEM NUMBER	ITEM DESCRIPTION	CONTRACT QUANTITY	UNIT	UNIT PRICE LABOR	UNIT PRICE MATERIAL	TOTAL UNIT PRICE	EXTENDED TOTALS
-------------	------------------	-------------------	------	------------------	---------------------	------------------	-----------------

Electrical Services

EL-1	Installation and connection of new underground electrical service from fire station to pump station, provision for connection to future Town Hall, and pump station control panel, connected and ready for service	1	LS	\$	\$	\$	\$
EL-2	Installation and connection of new underground electrical service from Ex. Service Building to Control Panels for Alarm Panel, Drip Pumps, and Flow Equalization Pumps connected and ready for service	1	LS	\$	\$	\$	\$
EL-3	Installation and connection of all wiring necessary for the operation of the remote zone valves and the remote zone valve heaters	1	LS	\$	\$	\$	\$
EL-4	Electrical Permits and Inspections	1	LS	\$	\$	\$	\$

=====

SUBTOTAL - ELECTRICAL: _____

Sanitary Sewers & Septic System

SAN-1	6" Sanitary Sewer	736	LF	\$	\$	\$	\$
SAN-2	8" Sanitary Sewer Replacement / Remove Ex. 6"	77	LF	\$	\$	\$	\$
SAN-3	Modifications/Connections to Ex. Septic Tank for 8" Inlet and 6" Outlet	1	LS	\$	\$	\$	\$
SAN-4	Remove Ex. Manhole / Replace with Clean out Manhole	1	EA	\$	\$	\$	\$
SAN-5	Sanitary Manhole	1	EA	\$	\$	\$	\$
SAN-6	Sanitary Pump Station Complete	1	LS	\$	\$	\$	\$
SAN-7	2" PVC Forcemain with Fittings and tracer tape	1	LS	\$	\$	\$	\$
SAN-8	Clean out installed in existing sanitary	1	LS	\$	\$	\$	\$

**MUNSON TOWNSHIP WASTE WATER TREATMENT SYSTEM
MUNSON TOWNSHIP, GEAUGA COUNTY, OHIO
BID SHEET 2 OF 4**

ITEM NUMBER	ITEM DESCRIPTION	CONTRACT QUANTITY	UNIT	UNIT PRICE LABOR	UNIT PRICE MATERIAL	TOTAL UNIT PRICE	EXTENDED TOTALS
Sanitary Sewers & Septic System - continued							
SAN-9	1050 Gallon Trash Trap and piping, installed and ready for service	1	LS	\$	\$	\$	\$
SAN-10	1500 Gallon Flow Equalization Tank and piping, installed and ready for service	1	LS	\$	\$	\$	\$
SAN-11	1500 gpd Multi-Flow aeration suspended media treatment tank and piping, installed and ready for service	1	LS	\$	\$	\$	\$
SAN-12	Drip Pump Station (2) complete, installed and ready for service	1	LS	\$	\$	\$	\$
SAN-13	Septic System Control/Alarm Panel complete, installed and ready for service	1	LS	\$	\$	\$	\$
SAN-14	Control Panel for Equilization complete, installed and ready for service	1	LS	\$	\$	\$	\$
SAN-15	Hydraulic unit for Drip System complete, installed and ready for service	1	LS	\$	\$	\$	\$
SAN-16	1.25" PVC supply line and fittings from hydraulic unit to drip field complete, installed and ready for service	1	LS	\$	\$	\$	\$
SAN-17	1" PVC common return line and fittings from drip fields to hydraulic unit complete, installed and ready for service	1	LS	\$	\$	\$	\$
SAN-18	Plowed in drip zones complete, installed and ready for service. Includes all fittings, header pipes, drip tubing, check valves, zone valves, heaters, air release valves, zone valves, etc. This item includes all tree or brush removal and disposal as necessary for installation, in accordance with Geauga Health Department Regulations	1	LS	\$	\$	\$	\$
SAN-19	4" underdrain from area of hydraulic unit to ditch area and ditch grading as necessary	1	LS	\$	\$	\$	\$
SAN-20	6" PVC Sanitary from existing inlet of existing septic system serving the service facility to the new trash trap complete	1	LS	\$	\$	\$	\$
SAN-21	Abandon existng forcemain	1	LS	\$	\$	\$	\$
SAN-22	Abandon/remove existing pump station	1	LS	\$	\$	\$	\$

MUNSON TOWNSHIP WASTE WATER TREATMENT SYSTEM
MUNSON TOWNSHIP, GEAUGA COUNTY, OHIO
BID SHEET 3 OF 4

ITEM NUMBER	ITEM DESCRIPTION	CONTRACT QUANTITY	UNIT	UNIT PRICE LABOR	UNIT PRICE MATERIAL	TOTAL UNIT PRICE	EXTENDED TOTALS
-------------	------------------	-------------------	------	------------------	---------------------	------------------	-----------------

Sanitary Sewers & Septic System - continued

SAN-23	Abandon existng septic riser	1	LS	\$	\$	\$	\$
SAN-24	Abandon existng Distribution Box	1	LS	\$	\$	\$	\$
SAN-25	Abandon existing leach field	1	LS	\$	\$	\$	\$
SAN-26	Permits and Inspections Septic System	1	LS	\$	\$	\$	\$
SAN-27	Septic System As-Built	1	LS	\$	\$	\$	\$

=====

SUBTOTAL - SEPTIC SEWERS & SEPTIC SYSTEM: _____

Miscellaneous

S-1	Proposed 10' Gravel Driveway	1	LS	\$	\$	\$	\$
S-2	Restoration, fine grading, and seeding	1	LS	\$	\$	\$	\$
S-3	Mobilization & Bonds	1	LS	\$	\$	\$	\$
S-4	Erosion Control	1	LS	\$	\$	\$	\$

=====

SUBTOTAL - MISCELLANEOUS: _____

TOTAL CONTRACT BID: \$

BF.13

MUNSON TOWNSHIP WASTE WATER TREATMENT SYSTEM
MUNSON TOWNSHIP, GEAUGA COUNTY, OHIO
BID SHEET 4 OF 4

The Bidder hereby acknowledges receipt of the following addenda:

ADDENDUM No.

DATE

ACKNOWLEDGED BY:

And We (or I) do hereby agree that in the event of failure on OUR part to contract as aforesaid (provided this Proposal is accepted) the Bid Bond, Check or Letter of Credit accompanying this Proposal shall be forfeited to the Owner as liquidated damages for the difference between this bid and the awarded Contract Price, not to exceed the amount of bond. We further agree that the Owner may reject any or all bids.

Submitted by: _____
Firm, Corporation or Individual

Address: _____

Phone Number: _____

Officer's Name and Title (typed): _____

Attest: _____
Secretary/Officer's Signature (print name below line)

(Seal - if Bid is by a Corporation)

Date: _____

Note: Evidence of authority to sign and the corporate seal must be affixed and attested by the Secretary.

Completion Date:

60 days after notice to proceed.

Liquidated Damages:

\$500.00 per day

BF.14